

Parallel Stacking Guide

for the Electriq Power

AC & DC-Coupled Inverters

Model Number: EPP-600-1005 (AC) EPP-600-1004 (DC)

V. 121120


1. Introduction

This is an addendum to the Electriq Power AC/DC-Coupled installation manual. Please refer to that document for warnings and basic installation instructions. This addendum defines specific changes for parallel stack operation only.

Note: The output real power (W) is reduced to 90% when system is in parallel.

		Three AC/DC-Coupled Inverters in parallel
AC rating output power	9 kW / 10 kVA	13.5 kW / 15 kVA


Example Diagram of Stacking the AC Systems



In parallel system, you will find the following items in the package:


- A parallel communication cable (RJ12 wire).
- Fused 6 AWG battery balancing wires.
- This guide book on parallel installation.

Example Diagram of Stacking the DC Systems



2. Mounting the Inverters

When installing multiple inverters, please follow below instructions on surrounding spacings.



For proper air circulation to dissipate heat, allow a clearance of approximately 6 inches (15 cm) to the side and approximately 8 inches (20 cm) above and below each inverter. Be sure to install each inverter in the same level.



3. Battery Connection

WARNING! Be sure that all inverters will share the same sets of batteries. The battery power terminal needs be paralleled, when system use multiple battery modules. Electric Power provides all wires for proper battery connection in an accessories box. They are:

a) 6 AWG and 8 AWG terminal block to battery cables.


b) 6 ft. 2 AWG terminal block to inverter wires. If longer wires are required use 0 AWG or larger with length equal to +/- 5.0% to carry a maximum load of 150 ADC.

c) Fused 6 AWG balancing wire. Provides less than 350 mVDC maximum offset between battery sets.


Note, if battery cabinet has five or six batteries, a 3/0 or 4/0 Polaris Connectors from your local electrical store will be required to connect the battery balancing wires. See image below.



Wiring diagram for three stack parallel system:



4. AC Input (Grid) Connection



Note:

- a) Connected grid wires (L1 and L2) to 40A breaker in grid tied main.
- b) Connect grid neutral conductor to main BUS neutral. DO NOT connect essential load neutral to main BUS neutral

Suggested cable requirement for AC input wires.


Inverter Grid Input wire requirements:

- a) Use wire rate for 40 AAC.
- b) All input wire length equal to +/- 5.0%.

NOTE: To keep the parallel inverters balanced be sure the grid wire lengths are as specified above.

5. AC Output (Load) Connection

Connect AC output of each inverter together. Refer to below figure for connection of AC output.



NOTE:

- a) Connected essential load wires (L1 and L2) to 30A breaker in essential load panel.
- b) Connect essential load neutral conductor to essential load panel neutral. DO NOT connect essential load neutral to main BUS neutral.


Suggested cable requirement for AC input wires.

Inverter Grid Input wire requirements:

- c) Use wire rate for 30 AAC.
- d) All essential load output wire length equal to +/- 5.0%.

NOTE: To keep the parallel inverters balanced be sure the essential load wire lengths are as specified above.

6. PV Connection




The PV Connections are the same as for a single inverter, shown as below:

NOTE: Please set the PV power rating for each DC-coupled system as close as possible, this ensures more consistent mode operation. The difference of installed PV power rating between each stacked inverter should be less than 500W.

7. Parallel Communication Cable Connection


An RJ12 cable is used for the Parallel systems to communicate between the inverters. Please follow the examples below to connect to the inverter.



Two inverters in parallel:




Three inverters in parallel:



8. Pre-Commissioning (Single Inverter Operation Check)

Verify that each parallel inverter can first operate by itself as a single inverter with no essential load (to prevent overloading) before setting them up for parallel operation. To do this,

- 1) Turn off the "LOAD INPUT" "FROM INVERTER" middle breaker on all parallel inverters.
- 2) Only turn on one and check inverter at a time.
- 3) Disconnect the parallel communication RJ12 cable for the unit under test.
- 4) Set the inverter "multi-Module" to single.
- 5) Turn the inverter off then on to reboot the inverter.



For detail on preforming the above steps, reference "System Setting" in **Installation Manual, Service & Users Guide for the AC & DC Coupled** for setting and operating the inverter using the display.

Next in the installation manual preform sections:


Waking Up the Batteries Operational Testing

WARNING, to prevent damage to the inverter's battery charger, turn battery on/off switch to OFF for 30 seconds then ON to put batteries into standby before each time the inverter battery disconnect circuit breaker is turned ON.

9. Commissioning (Parallel Operation)

To operate the system in parallel mode:

- 1) Only turn on one inverter at a time and put inverter in "Multi-Module" to parallel
- 2) With the inverters off connect the parallel communication RJ12 cable. See section above for details.
- 3) With the inverter off turn on the "LOAD INPUT" "FROM INVERTER" middle breaker on all parallel inverters
- 4) Turn on the parallel inverters. Note first inverter to boot is the MASTER (INV M). See images below for MASTER (INV M) and SLAVE (INV S) icons.



If there are no fault alarms, the parallel system is ready to commission using the smart phone commission app.

10. Specifications of the AC-Coupled System in Parallel

	2 inverters in parallel	3 inverters in parallel	
SOLAR AC INPUT			
Maximum Breaker Size on PV Input (per inverter)	20 A / 20 A	20 A / 20 A /20 A	

11. Specifications of the DC-Coupled System in Parallel

	2 inverters in parallel	3 inverters in parallel
SOLAR DC INPUT		
Maximum Power (Total)	13 kW	19.5 kW
Maximum Power (Per Channel)	3250 W	
Operation / MPPT Voltage Range	120 to 500VDC / 250 to 430VDC	
Minimum Start Voltage	150VDC	
Number of MPPT channels	4 channels	6 channels
Maximum Current per MPPT Channel	13 A	

12. Specifications of the AC/DC-Coupled System in Parallel

AC OUTPUT TO LOAD		
Power (Continuous) @ 25°C	9 kW / 10 kVA	13.5 kW / 15 kVA
Overload 40/5/1sec @ 25°C	11 / 13 / 15 kW	16.5 / 19.5 / 22.5 kW
Rated Output Current	42A (@120V and 240 V)	63A (@120V and 240 V)
Frequency (Selectable)	50/60Hz	
Voltage	L-N: 120V ± 3%; L-L: 240V ± 3%	
Total Harmonic Distortion (THD)	< 5% at rated power	
AC INPUT FROM GRID (GRID SUPPORT)	ì	
Voltage Limits (Bypass)	L-L: 180 to 280V (240 V nominal)	
Frequency Range (Bypass)	55 to 65 Hz	
Automatic Transfer Relay Rating	70A	105A
Typical Transfer Time	20ms	
AC OUTPUT TO GRID		
Current Range (Mode-dependent)	0 to 48A (@240V)	0 to 72A (@240V)
Voltage Range	L-L: 211 to 264V ± 3.0V	
Frequency Range	59.4 to 60.4Hz ± 0.05Hz	
EFFICIENCY	·	
Peak PV to Grid	96%	
CEC weighted PV to Grid	95.5%	
DC BATTERY CHARGER		
Maximum Charge Current	120A	180A
Output Voltage Range	(44 - 52) 48V (Nominal)	
Chemistry	INR - NMC - Lithium manganese nickel	
Battery Capacity Range	27 kWh to 67 kWh	40 kWh to 101 kWh

GENERAL SPECIFICATIONS		
NEMA/IP Protection Rating	NEMA Type 1 Indoor / IP20	
Minimum Starting Temperature (Inverter)	0 °C	
Operating Temperature (Battery Charging)	5 °C to 50 °C	
Operating Temperature (Battery Discharging)	-10 °C to 50 °C	
Storage Temperature (Battery)	-20 °C to 20 °C	
Storage Temperature (Inverter)	-20°C to 55°C	
Compliances	UL1741SA, UL1973, UL9549, IEEE 1547, FCC Class B	